



NOTES:

1. CONCRETE CHANNEL BOTTOM SHALL HAVE 6" CURBS.
2. CONCRETE SHALL BE 6" THICK WITH 3000 PSI COMPRESSIVE STRENGTH.
3. CONCRETE SHALL BE REINFORCED WITH #3 BARS ON 18" CENTERS.
4. 2" MINIMUM DIAMETER WEEPHOLES WITH MIRAFI 140NS FILTER MEDIA OR APPROVED EQUAL SHALL BE PLACED AT INTERVALS NO GREATER THAN 25'.
5. CONCRETE SHALL HAVE TRANSVERSE JOINTS AT WEEPHOLE LOCATIONS. REDWOOD EXPANSION JOINTS ARE REQUIRED A MAXIMUM OF EVERY 200 FEET. CONSTRUCTION JOINTS PLACED WHEN PAVING OPERATION HAS CEASED FOR MORE THAN 30 MINUTES.
6. SIDESLOPES AND MAINTENANCE SHELVES SHALL HAVE ADEQUATE STAND OF VEGETATION PRIOR TO ACCEPTANCE.

D-10	CHANNEL	
CITY OF BURLESON		
ORIGINAL	10/6/06	SWC
REVISION		
REVISION		
REVISION		